
BULLETIN #2024 – 02

July 22nd, 2024

CLADDING REQUIREMENT PRIOR TO INSULATION INSPECTION

To enhance the efficiency of cladding inspections and mitigate concerns regarding water ingress during insulation inspections, **effective immediately**, cladding (including roof flashing) must be installed and fully completed before scheduling any insulation inspection.

This approach will mitigate health and safety concerns within the building and reduces the risk of inspection failures.

Please disseminate this information to all site offices.

Thank you for your cooperation in implementing this important change.

The Town of Whitby
Building Services
building@whitby.ca
905-430-4305